



FACILITIES MANAGEMENT AND ANCILLARY SERVICES


BUILDING DESIGN STANDARDS

FURNISHING - DIVISION 12

Foot Grilles - 12 48 20



- pipe shall be coordinated on site: minimum 100mm depth shall pass below the bottom of the concrete slab so as to allow junction with a mechanical joint.
- .2 Shall install a P-Trap with a cork of draining and shall be located so as to be accessible for maintenance.
 - .3 Shall have trap seal primer.
 - .4 Connect a water supply drain to trap seal so as to allow for a continuous flow through the drain.
 - .5 Two (2) coats of flexible cement-based waterproofing membrane on concrete slabs under pan and pipe opening are required. Acceptable product: "Mapelastic315", as manufactured by Mapei, or approved equivalent.



Part 3 Execution

3.1 General

- .1 All sides of the pan that are in contact with a concrete surface must be covered with two (2) layers of flexible cement-based waterproofing membrane. Acceptable product: "Mapelastic315", as manufactured by Mapei, or approved equivalent.
- .2 The installation of the foot grille in a sand coat is forbidden. Specify levelled concrete.

END OF SECTION